City of Scott City

Requesting Inspections:

You may request inspections by calling City Hall at 620-872-5322 or Jerek Wasinger at 620-874-8255.

Required Inspections/Sequential Order:

The following is a list of typical inspections required. Please note that it is the responsibility of the permit holder to coordinate all inspection activity.

- A. <u>Temporary Power:</u> if required. (Must meet NEC & Wheatland Electric standards)
- B. <u>Footing Inspection:</u> Made prior to placement of concrete. To be made after all column or wall footings are excavated and forms erected, and any required reinforcing steel is in place.
- C. <u>Foundation Wall Inspection:</u> Made prior to placement of concrete. To be made after all forms are set and overlapping reinforcing steel is tied together (included all foundation and piers).
- D. <u>Backfill inspection:</u> Made prior to backfilling of foundations. To be made after damp proofing of foundations have been accomplished.
- E. <u>Under slab Inspections:</u> Made after foundation has been backfilled and after all under slab plumbing, mechanical, electrical components and piping have been installed.
- F. <u>Floor slab (basement-garage-stoop) Inspections:</u> Made prior to placement of concrete. To be made after all reinforcing steel-wire-mesh is in place and all under slab mechanical, plumbing and electrical work has been inspected and approved.
- G. <u>Masonry Fireplace Inspection:</u> Made after the firebox is built and the flue liner is in place.
- H. <u>Rough-in inspection:</u> Made prior to concealment (do not insulate or cover without prior approval). Framing, fire blocking, plumbing, electrical and mechanical will typically be done at this time.
- Electrical Service Inspection: Done at time of rough-in inspection. Made after service panel and all associated conductors and grounding are complete.
- J. <u>Fuel Gas line Inspection:</u> Made after all appliances-gas piping systems-vents are installed. Pressure test is required at inspection.
- K. <u>Final Inspection:</u> Made after all work is complete, prior to the dwelling being occupied.